QUALITY CONCRETE PRODUCTS, INC
4200 78th St SW - PO Box 1609
Mukilteo, WA 98275
(425) 355-5510 / fax (425) 355-5559

ESTIMATE SHEET

job name:	Legacy	contractor:		date:	2/24/2015
				bid date:	
location:	2601 - 76th Ave SE	contact:	Rich	phone #	
	Mercer Island	site contact:	Jeff (206) 427-4578	fax #	
				PO #	

DESCRIPTION	RIM ELEV.	INV. ELEV	SUMP	HEIGHT	QTY	MATERIALS	UNIT COST	TOTAL
OWS-1					1	36x36 Oil / Sand Separator	349	349.00
					1	36x36x6" riser w/ 37.5 x 39.5 opening	82	82.00
					1	37.5 x 39.5 HDG - H20 grate	798	798.00
					2	cored holes	25	50.00
					2	s-106-7 boots	60	120.00
OWS-2					1	36x36 Oil / Sand Separator	349	349.00
					1	36x36x6" riser w/ 37.5 x 39.5 opening	82	82.00
					1	37.5 x 39.5 HDG - H20 grate	798	798.00
					3	cored holes	25	75.00
					1	s-106-7 boots	60	60.00
					2	s-406-12C boots	60	120.00
Floor Drains					4	type 40 basin	92	368.00
					4	EJ 00772002 - 14/20 frame and grate	128	512.00
					4	cored holes	25	100.00
					4	s-106-7 boots	60	240.00
type 241					1	cb-12- type 1P	185	185.00
					2	cb-6" riser	42	84.00
					1	cb-4" riser	38	38.00
					2	s-406-12C boots for 6" pipe	60	120.00
					2	cored holes	25	50.00
					1	EJ 0077704B01 - 20/24 frame and solid lk	238	238.00
type 241					1	cb-12- type 1P	185	185.00
					2	cb-6" riser	42	84.00
I can only core and boot for the N and S					1	cb-4" riser	38	38.00
pipes there is not enough room between					2	s-406-12C boots for 6" pipe	60	120.00
the two 12" holes for the 2 pipes on					4	cored holes	25	100.00
the W side to withstand the expansion					1	EJ 0077704B01 - 20/24 frame and solid lk	238	238.00
of the boot. I can core two 10" holes								
that you can use with a sand collar for the								
W pipes								

15-059

QUALITY CONCRETE PRODUCTS, INC
4200 78th St SW - PO Box 1609
Mukilteo, WA 98275
(425) 355-5510 / fax (425) 355-5559

ESTIMATE SHEET

job name:	Legacy	contractor:		date:	2/24/2015
				bid date:	
location:	2601 - 76th Ave SE	contact:	Rich	phone #	
	Mercer Island	site contact:	Jeff (206) 427-4578	fax #	
				PO #	

DESCRIPTION	RIM ELEV.	INV. ELEV	SUMP	HEIGHT	QTY	MATERIALS	UNIT COST	TOTAL
48" manhole					1	48x5' base sp w/ steps	452	452.00
					1	48 top slab 0	160	160.00
					1	4" grade ring	25	25.00
					1	6" grade ring	60	60.00
					2	s-406-12C boots	60	120.00
					1	EJ 00371582 - 6/24 ring and cover DRAIN lk	285	285.00
					1	pail pipe lube	20	20.00