EXXEL PACIFIC
GENERAL CONTRACTORS

Subcontract Change Order

Distribution
- [ ] One Way Plumbing LLC
- [ ] Office
- [ ] Field

Project: 201602. The Cora Apartments (19 W Harrison)
19 W Harrison
Seattle, WA 98109

Change Order #: 4
Change Order Date: 3/8/17
Subcontract #: 201602ONELLC

To (Subcontractor): One Way Plumbing LLC
127 10TH St So., Ste 200
Kirkland, WA 98033

You are directed to make the following changes in this SubContract:

PCO	ACO	Description	Phase	Amount
73	ICO #14	Plumbing Systems **PCO #073 - Gas Permit for Temp Heat** *One Way Plumbing pricing for gas permit and associated work for provision for temp heating. Reference One Way Plumbing COR dated 2/20/17 for pricing.*	L1.220000.	650.00
27	4	Plumbing Systems **ASI 002 - Activity Rm. Revisions** *ASI 002 - Activity Rm. Revisions - Plumbing* *Reference One Way Plumbing change order request #3, dated 11-14-2016, to furnish and install Elkay ELUHAD211550 stainless steel sink w/Delta ~~9959-CZ-DST bronze faucet.~~ Added waste/water/vent rough-in for added sink, icemaker & dishwasher, core drilling and trim. Price excludes start-up/testing of appliances, installation of undermount sink, drilling of countertop for sink and faucet holes.* *Total sum - $2,140.00*	L1.220000. 9959-AR-DST SS Faucet	2,140.00
72	6	Plumbing Systems **Rough-in for Future Cold Water Meters in Residential Units** *Subcontractor to install (75) spacer tubes and couplings for future cold water meters (Supply by others). Reference One Way Plumbing COR dated 2/20/17 for pricing.*	L1.220000.	607.00
47	4	Plumbing Systems **RFI #065.1 - BBQ & Fire Pit at Rooftop Deck** *RFI #065.1 - BBQ & Fire Pit at Rooftop Deck - Plumbing* *Reference One Way Plumbing, LLC COR #8, dated 02-09-17* *- to install sink with shut-offs and drain down - $1,951.00* *- to add heat trace - $1,620.00* *- to add gas outlet boxes - $2,050.00* *Total cost: $5,620.00*	L1.220000.	5,620.00
		Total		**9,017.00**

Not valid until signed by both the Subcontractor and Contractor. Signature of the Subcontractor indicates the Subcontractor's agreement herewith, including any adjustment in the Subcontract Sum or Time.

The original Subcontract Sum was	**1,179,300.00**
The net change by previously authorized Change Orders was	**12,971.00**
The Subcontract Sum prior to this Change Order was	**1,192,271.00**
The Subcontract Sum will be increased by this Change Order	**9,017.00**
The new Subcontract Sum will be	**1,201,288.00**

Authorized By Contractor:
Exxel Pacific, Inc.
323 Telegraph Road
Bellingham WA 98226
By: B Bjorn
Date: 3/8/17

Accepted By Subcontractor:
One Way Plumbing LLC
127 10TH St So., Ste 200
Kirkland, WA 98033
By: M Ohm
Date: 3/13/17

Change Order Request

February 20, 2017

Exxel Pacific
4220 Aurora Avenue N.
Seattle, WA 98103
Attn: Ben Prigmore

Re: Cora Apartments – Change Order Request #10 Gas Permit for Temp Heat

Ben,

Total cost to pull a gas permit for the temp heat is $565 + 15% OH&P = $650. Let me know if you have any questions or require further information.

Sincerely,

Richard Donelson
Project Manager / Estimator
richd@owpllc.net
425-591-4296 cell

Change Order Request

November 16, 2016

Exxel Pacific
4220 Aurora Avenue N.
Seattle, WA 98103
Attn: Victor Vo

Re: Cora Apartments – Change Order Request #3r1 – ASI-002 Activity Room Revisions

Victor,

Per ASI-002, an Elkay ELUHAD211550 stainless steel undermount sink with Delta 9959-AR-DST stainless steel faucet, icemaker and dishwasher is being added to the Level 2 Activity Room. Total cost for added waste/water/vent rough-in, core drilling and trim is $2,140. Price excludes startup/testing of appliances, installation of undermount sink, drilling of countertop for sink and faucet holes.

Please issue an official Change Order at your earliest convenience. Let me know if you have any questions or require further information. Thank you.

Sincerely,

Richard Donelson
Project Manager / Estimator
richd@owpllc.net
425-591-4296 cell

Change Order Request

February 20, 2017

Exxel Pacific
4220 Aurora Avenue N.
Seattle, WA 98103
Attn: Ben Prigmore

Re: Cora Apartments – Change Order Request #9 Install Meter Jumper on Cold Side

Ben,

Total cost to RE-prefabricate all cold side shutoff valves to include a spacer and unions for future installation of a meter is $528 + 15% OH&P = $607. Spacers and unions provided by others. Meter supply and install by others. Let me know if you have any questions or require further information.

PLEASE NOTE: The added spacers and unions increase the chance of a leak in the future. We recommend these are not installed unless it is certain that a meter is going to be installed. A meter can always be cut into the pex at a later date if they ever decide to install the meters.

Sincerely,

Richard Donelson
Project Manager / Estimator
richd@owpllc.net
425-591-4296 cell

Change Order Request

February 9, 2017

Exxel Pacific
4220 Aurora Avenue N.
Seattle, WA 98103
Attn: Ben Prigmore

Re: Cora Apartments – Change Order Request #8 RFI-065.1 Rooftop Sinks, BBQ

Ben,

Total cost for RFI-065.1 is broken down below. Total cost is $5,620. Please issue an official Change Order at your earliest convenience. Let me know if you have any questions or require further information. Thank you.

Install sink with shutoffs and drain-down: **$1,950**

- This option would involve installing shutoffs in the hallway ceiling below the sink. We would need to route the water to the nearest autowash so the maintenance person can shut off the sink and then drain all the water out of it. They would need to make sure they do this yearly so the sink doesn't freeze.
- Excludes access panels (which will need to be fire rated). Excludes faucet and sink. Also excludes the countertop at the BBQ.

Add heat trace: **$1,620**

- In addition to the option described above, we could install heat trace on all of the piping below the countertop, all the way up to the bottom of the faucet. Note, there is no way to heat trace the faucet itself. There will be some heat that will travel up into the faucet from below that will help prevent it from freezing, but if there were a really cold day, the faucet is eventually going to freeze and break.
- Excludes electrical connections.

Add gas outlet boxes: **$2,050**

- Excludes placement and hookup of gas appliances. I only included the gas connection at the outlet box, so the appliance installer will have to connect to our box.

Sincerely,

Richard Donelson
Project Manager / Estimator
richd@owpllc.net
425-591-4296 cell